JHARKHAND STATE CRICKET ASSOCIATION

INTERNATIONAL STADIUM COMPLEX, H.E.C. CAMPUS, DHURWA, RANCHI- 834004.

JSCA/RNC/226/475/2024-25

17th January, 2025

Name of Work:

Drilling of Bore well approach road and other miscellaneous jobs at JSCA ground at Kanko Math, Katras, Dhanbad.

INVITATION OF TENDER

Tenders are invited from experienced and bonafide agencies for "Boring and approach road at JSCA ground at Kanko Math, Katras, Dhanbad".

SCOPE OF WORK:

As per Bill of Quantities (B.O.Q.) and as required at site for subject work. In case, adequate yield is not found, boring at other location may have to be done. Boring cost shall be made for the same.

2. ELIGIBILITY CRITERIA: -

Bidder must fulfill the following eligibility criteria

- Should have valid GST registration;
- Must have executed a single civil work of Rs.30 Lakhs in the last three financial years;

3. AUTHORITY OF PERSON SIGNING TENDER DOCUMENT: -

A person signing the tender form or any documents forming part of tender/contract on behalf of the bidder, should be authorized to do so. A letter of Authority should be submitted alongwith tender.

EARNEST MONEY: -

EMD of Rs.10,000/- (Rupees Ten Thousand only) in the form of Demand Draft payable to Jharkhand State Cricket Association at Jamshedpur.

5. PRICE:

The tenderer shall quote as per bill of quantities enclosed at Annexure-1 of the tender. Quoted price shall include, all cost of material labour, transportation, handling, taxes, incidentals, overheads, margin, etc. as applicable excluding GST which shall be added separately in the B.O.Q total

6. TENDER SUBMISSION:

Tender documents shall be submitted in two parts (packets):-

Part-1 Technical

(Packet-1) shall contain following documents:

- Covering letter of Tenderer;
- Credentials that makes bidder eligible i.e. copy of order for Boring job and completion certificate;
- Demand Draft for EMD. of Rs.10,000/- (Rupees Ten Thousand only);
- Any clarification tenderer may like to seek.

* Part-2 Financial

(Packet- 2) shall contain only the price schedule.

JHARKHAND STATE CRICKET ASSOCIATION

INTERNATIONAL STADIUM COMPLEX, H.E.C. CAMPUS, DHURWA, RANCHI- 834004.

Packet- 1 shall be opened first. Packet- 2 shall be opened only for those agencies whose all documents including the earnest money are found in order. Bidders shall have no claim for such rejection.

7. PLACE AND DATE OF SUBMISSION OF TENDER:

Bids can be submitted till 04:00 PM on 28th January, 2025 in the office of C.E.O. in 1st Floor of Amitabh Choudhary Pavilion at J.S.C.A. International Stadium Complex, Dhurwa, Ranchi.

8. PAYMENT:

Only one Bill after completion of work.

9. SECURITY DEPOSIT:

Security deposit shall be deducted from on account bill @5% of the executed value. It will be refunded after successful completion of defect liability period.

10. TIME OF COMPLETION:

The work should be completed within 30 (thirty) days from the date of issue of LOI.

11. DEFECT LIABILITY PERIOD:

The defect liability period shall be one year from the date of certified completion of work.

12. NO COMPENSATION FOR TENDER SUBMISSION:

Intending tenderers shall submit their tender at their own cost and no compensation shall be payable for expenditure incurred, if any.

Jharkhand State Cricket Association (JSCA) reserves the right to reject any/all tender without assigning reasons whatsoever.

Tender document can be downloaded from website: www.cricjharkhand.org

For Jharkhand State Cricket Association

(A.K. Singh) C.E.O.

Page 2 of 4

JHARKHAND STATE CRICKET ASSOCIATION

INTERNATIONAL STADIUM COMPLEX, H.E.C. CAMPUS, DHURWA, RANCHI- 834004.

ANNEXURE - 1

BILL OF QUANTITIES

(Rates to be quoted both in figures and words)

SI. No.	Item Description	Unit	Qty.	Rate		Amount
	€.			In figures	In words	7.111.04.111
1.	Drilling of deep bore well to of size 8" i.e. 200mm dia up to the hard rock strata with an overlap with the hard rock strata and drilling of 6 1/2" size bore in hard rock at on location.			3		· ·
(a)	Drilling of suitable size borewell to accommodate 8" pipe	Rft	50			
(b)	Drilling of 6 - 1/2" dia size bore in rock strata	Rft	600			
2.	Supplying, assembling, lowering and fixing in vertical position in borewell CPVC suitable pipe of 2"or 1.5" dia as per requirement including hire & labour charges, fittings					
(a)	For use of 2" dia pipe	Rft	250			
(b)	For use of 1.5" dia pipe	Rft	250			
3	Design manufacturing, supply, erection, testing and commissioning of water lubricated submersible deep borewell pump of KSB/CRI/Texmo make suiting to requirement (Any one of following pump to be provided)					
(a)	For use of 5HP pump	Each	1			
	ALTERNATIVELY					
(b)	For use of 7.5HP pump	Each	1			
4.	Brick work in common burnt clay bricks of class 7.5 in drain wall up to ground/as per requirement at site in cement mortar 1:6	Cum	40			
5.	Supplying MS pipe of 3" dia NB (medium duty) including jointing by welding to make pipe of length 10m with necessary hooks at intermediate level for fixing of nylon net as per requirement and erecting on concrete block provided with 4nos of 16mm dia bolts with all bye works complete including applying of 2 coats of synthetic enamel paint over two coats of zinc chromate primer.	Kg	1000			

SI. No.	Item Description	Unit	Qty.		Rate	Amount
				In figures	In words	
6.	Modification, repairing, straighten bent members on existing gate suiting to requirement for entry of vehicles including welding new members and applying 2 coats of synthetic enamel paint after scrapping of existing paint completely (Payment for new members will be paid under item no 7 appx. size - 12'x5'	Lot	LS			
7.	Fabrication of new gate including supply of materials for man entry and fixing it to RCC columns completely	Kg	50			
8.	Supply and spreading of GSB material from crushed stone aggregates of 150mm compacted thickness for formation of 5.0m wide road with central camber and both side slope of 50mm from outside road up to pitch with all bye works like dry rolling, wet rolling complete	Cum	50			s
9.	Supplying, fabricating and fixing name board made from MS sheet of 1mm thickness in semi-circular shape on existing gate pillars using 25x25 mm angle as stiffener (2 nos.) one at top and one at bottom in rear side of MS sheet including 2 coats of synthetic enamel paint over a Zinc chromate primer in all respects complete.	kg	50		æ	
10.	Supply and laying of 100 mm thick compact muram with compaction by watering and rolling completely as per requirement.	Cum	50			
	SUB-TOTAL					
	GST AMOUNT					
	GRAND TOTAL					

(Rupees in words:	
-------------------	--

SIGNATURE OF THE BIDDER

DATE:

STAMP